



**Bill of Material  
Solerus Energy**

**Ref.: 1620791020**

Bill to  
**Matt Uhlman**  
**1017 Fellows Drive**  
**Yakima, WA 98908**

Ship to  
**Matt Uhlman**  
**1017 Fellows Drive**  
**Yakima, WA 98908**

Supplier Solerus Energy  
Address 22525 SE 64th Place #200  
Issaquah, WA 98027  
Contact \_\_\_\_\_  
Phone 844.765.3787  
email \_\_\_\_\_

Requisition Date 10/7/2016  
Requested By SM  
Account # \_\_\_\_\_  
Ref. # 2079Uhlman  
Approved By SM

Quote #	Due Date	Ship Via	Service Type	Terms
online	11/7/2016	Freight	Ground	Prepaid

P/N	Description	Unit of Measure	Order QTY	Unit Cost	Extended Cost
Primo 12.5-1	Fronius Primo 12.5-1 String Inverter	ea	1		
CSI 265W	CS6K-P-265 Polycrystalline Solar Panel 60 Cell	ea	52		
D223NRB	D223NRB, 100A, 240V, 2P, FUSIBLE, NEMA3R	ea	1		
PVWIRE15	PV OUTPUT, HELIOS H4, MALE/ FEMALE, 10/1, 15FT, 1000 V,	ea	5		
PVWIRE100	PV OUTPUT, HELIOS H4, MALE/ FEMALE, 10/1, 100FT, 1000V,PVWIRE	ea	5		
PVWIRE50	PV OUTPUT, HELIOS H4, MALE/ FEMALE, 10/1, 50FT, 1000V,PVWIRE	ea	5		
XR-100-132B	XR100 RAIL 132" (11 FEET) (Black)	ea	9		
XR-100-168B	XR100 RAIL 168" (14 FEET) (Black)	ea	0		
XR-100-204B	XR100, Rail 204" (17 Feet) Black	ea	16		
FM-FF1-002	Kit, 6pcs, FlashFoot, Mill	ea	11		
UFO-CL-001-B	Kit, 4pcs, Universal Module Clamp	ea	30		
UFO-STP-40MM-B	Kit, 4pcs, Stopper Sleeve, 40MM, Black	ea	7		
MI-BHW	Kit, 2pcs, 1/4 x 1/4 Microinverter Mounting, Bonding T-Bolt FOR RSD MOUNTING	ea	8		
XR-100-CAP	Kit, End Cap XR100 (10 sets per bag)	ea	2		
29-4000-077	Wire Clips, Molded PVC Black, Polybag 20	ea	1		
XR-100-SPLC-BD	Kit, XR100 Bonded Splice	ea	14		
GD-LUG-003	Kit, 2pcs, Grounding Lug, Low Profile (EQUIPMENT GROUNDING)	ea	8		
RSD	Fronius Multi-String Rapid Shut Down (NOT INCLUDED)	ea	2		
WEEB-11.5	WILEY WEEB GROUNDING CLIP , WEEB-11.5 FOR RSD MOUNTING	ea	10		
		FedEx <input type="checkbox"/>	Freight <input checked="" type="checkbox"/>	Shipping	
				Total	

Reason for ordering the above purchase(s): \_\_\_\_\_ Site Order  Project \_\_\_\_\_

**REMARKS:**

Form Revision 06/01/12